

Name of the Road :-

Construction of Aamli Fala Bridge and Road

Block :-

Dungarpur

District : DUNGARPUR

Length


4.00 Km

GENERAL - ABSTRACT OF COST

Based on PWD Circle Dungarpur Road BSR-2019

S.No.	Particulars	Amount
1	Part A Earth Work	4196895.00
2	Part B WMM & Hard Shoulder	4525373.00
3	Part C B.T. Work	2298978.00
4	Part D Road Furnishing	690929.00
5	Part E C.D. Works	31415309.00
Total Rs :-		43127484.00
Add 1.50 % Contingencies		1.50% 646912.00
Add 1 % Q.C. Charges		1% 431275.00
Total Rs :-		44205671.00
Add 13% Prorata Charges		13% 5746737.00
G. Total :-		49952408.00


Say Rs :- 500.00
Lacs

*and amount here
has as per BSR Road 2022*

(Pavan Kumawat)
Assistant Engineer
PWD Sub Dn Jhonthri


(JK Jain)
Executive Engineer
PWD Dn Dungarpur

TS/SE/DPR/No. 17 Dated 25/5/2023
Rs. 500 Lacs (Word Rupees Five Hundred only)
Head 5051-03-337-01 (74)


T. A. to S. E.
P.W.D. Circle Dungarpur


Superintending Engineer
P.W.D. Circle Dungarpur

TECHNICAL REPORT

: Construction of Aamli Fala Bridge and Road

1 NAME OF WORK

2 Sanction Authority

संयुक्त सचिव पथ, सार्वजनिक निर्माण विभाग, जयपुर
मुख्य अभियंता एवं अतिरिक्त सचिव, सार्वजनिक निर्माण
विभाग, जयपुर पत्रांक एफ 7 (57)/अनु II/2023.
24/डी-363 दिनांक 03/05/2023

JOB No

3 CATEGORY & NO. OF ROAD

: VR-

4 CHAINAGES OF STARTING & END
POINTS OF PROPOSED WORK

:

5 LOCATION

:

6 NAME & CHAINAGE OF IMPORTANT
VILLAGE COVERED IN WORK

:

7 CATEGORY OF ROAD SH/MDR

: VR-

8 DISTRICT

: Dungarpur

9 ASSEMBLY CONSTITUENCY

: Dungarpur

9 Name of MLA

: Sh. Rajkumar Roat (Chorasi)

0 Name of MP

: Sh. Kanakmal Katara

1 PROPOSED LENGTH OF ROAD (KM)

: 4.00 Kms

2 EXISTING CARRIAGEWAY WIDTH
(Mtr.)

Track

3 NECESSITY OF WORK

: The Proposed shortest road to Connected Amli Fala PHQ
of Jhontri Block which is 4.00 Km length with Bridge

4 TRAFFIC DETAILS (PCU)

: The PCU on this road is 2342 as per latest traffic census
and 30 CVPD

5 PROPOSED WORK DETAILS

The work shall be carried out as per MoRD
Specification, and relevant IRC Specifications

Sub base

Base course

: One layer of GSB of 150mm thickness

: WMM of 150mm Thick

Primer

: Primer coat with bituminous Emulsion @ 6 kg/10 sqm
as per Morth Cl. 502, 112

Tack coat

: Tack coat with Bituminous VG-10 @0.2 kg per sqm as
per clause 503. as per Morth Cl. 502, 112.

BT
Surfacing
Berms

- : 20 mm PMC and Seal Coat Type-B
- : 150mm thick Earthen Shoulder 1.875 Mtr width on both sides.

Road Furnishing :-
Traffic Signs

Retro-reflectorised Cautionary, Mandatory and Informatory sign Boards as per IRC: 67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 shall be provided on required locations as per Technical Specifications Clause 801.

Direction and place identification signs

- : Retro-reflectorised Cautionary, Mandatory and Informatory sign Boards as per IRC: 67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 shall be provided on required locations as per Technical Specifications Clause 801

Information board

- : Typical citizen's information board as per MORD specifications and drawing shall be provided at starting of BT road work.

Specifications of CD works:
Foundation concrete

- : 200mm thick PCC M-10 Grade Nominal mix 1:3:6 as per clause 802, 803, 1202 & 1203

Concrete

- : Plain Cement Concrete M-15 Proposed in H.P.Culvert Head Wall

Finishing

- : Cement plaster in CM 1:4 as per Clause 613.3 & 1208.4

Coping

- : PCC M-20 coping 75mm thick as per Clause 615.710 & 1204.3.11

Hume Pipe

- : NP-3, 1000mm dia ISI Marked

SPECIFICATION

- : For the preparation of the estimate specification are based on IRC/MoSRTTH specificatins

BASIS OF RATES

- : Current BSR of Circle Dungarpur.- 2022 have been followed.

Probable date of Completion

- : The work shall be Completed within 8 Months after work award.

Estimated Cost (Rs in Lacs)

- : **500.00**

Name of S.E.

Shri R.C. Meena SE PWD Circle Dungarpur


Name of E.E.

O : 02964-230292

Name of A.E.

Shri JK Jain

Sh.Pavan Kumawat


(Pavan Kumawat)
Assistant Engineer
PWD Sub Dn Jhonthri


(JK Jain)
Executive Engineer
PWD DIVISION DUNGARPUR

No.	Description of Item	Quantity	Rate (Rs)	Unit	Amount (Rs)
1	2	3	4	5	6
1	Part "E" CD Work				
B-1	Earthwork in excavation for foundation of structure complete with all lift, dewatering, shoring and shuttering etc. including refilling of trenches in 250 mm layer, ramming, watering and disposal of surplus soil within a lead of 1000 meters, as per drawing and technical Earth in excavation for foundation of specification. [MoRTH Specification : Clause 304]. In ordinary soil [MoRTH Specification : clause 301] BY MECHANICAL MEANS Depth upto 3m				
1.4	1000mm dia HP 1 Row	681.84 cum	57.00	P.Cum	38865.00
	1000mm dia HP 2 Row	450.80 cum	57.00	P.Cum	25696.00
	RCC Bridge	617.02 cum	57.00	P.Cum	35170.00
	Syphon	95.84 cum	57.00	P.Cum	5483.00
	Retaining wall	1680.00 cum	57.00	P.Cum	95780.00
	VCW	1252.50 cum	57.00	P.Cum	71393.00
		4778.00			272347
2	Earthwork in excavation for foundation of structure complete with all lift, dewatering, shoring and shuttering etc. including refilling of trenches in 250 mm layer, ramming, watering and disposal of surplus soil within a lead of 1000 meters, as per drawing and technical Earth in excavation for foundation of specification. [MoRTH Specification : Clause 304]. In Ordinary/Soft rock (not requiring blasting) [MoRTH Specification : Clause 301] BY MECHANICAL MEANS				
B-1					
1.3.2					
	RCC Bridge	662.46			
		666.27 cum	83.00	P.Cum	55300.00
3	Earthwork in excavation for foundation of structure complete with all lift, dewatering, shoring and shuttering etc. including refilling of trenches in 250 mm layer, ramming, watering and disposal of surplus soil within a lead of 1000 meters, as per drawing and technical Earth in excavation for foundation of specification. [MoRTH Specification : Clause 304]. In Hard Rock [MoRTH Specification : Clause 301, 302, 303]. Blasting Prohibited				
B-1					
1.4.2					
	RCC Bridge	456.27			
		456.27 cum	670.00	P.Cum	305701.00
4	Plain Cement Concrete 1:3:6 with 40mm nominal mix in foundation with crushed stone aggregate 40mm nominal size mechanically mixed, placed in foundation and compacted by vibrator including curing for 14 days. (MoRTH specification clause : 2100)				
B-2					
5					
	1000mm dia HP 1 Row	46.44 cum	3038.00	P.Cum	141085.00
	1000mm dia HP 2 Row	26.80 cum	3038.00	P.Cum	81418.00
	Retaining wall	167.99 cum	3038.00	P.Cum	510354.00
	VCW	80.70 cum	3038.00	P.Cum	245167.00
		321.93			978244

S.No.	Description of Item	Quantity	Rate (Rs)	Unit	Amount (Rs)
1	2	3	4	5	6
5	Structural cement concrete (Design Mix) in open foundations, with form work, at any level. Cement concrete for plain/reinforced concrete in open foundations as per drawing and technical specification. [MoRTH Specification : Section 1700 & 1500]. With 20mm nominal size aggregate P.C.C. M-20 grade	71.20 74.43 cum	4017.00	P.Cum	298985.00
6	Structural cement concrete (Design Mix) in open foundations, with form work, at any level. Cement concrete for plain/reinforced concrete in open foundations as per drawing and technical specification. [MoRTH Specification : Section 1700 & 1500]. With 20mm nominal size aggregate R.C.C. M-25 grade	8 cum			
7	Providing and laying Plain Cement Concrete M-15 mix with stone aggregate 20mm nominal size mechanically mixed and vibrated in foundation upto a depth of 1.50 below ground level and or 1.50mtr. above ground/bed level.	465.18 cum	4341.00	P.Cum	2019346.00
8	Providing and laying Plain Cement Concrete M-15 Mix with stone aggregate 20mm nominal size mechanically mixed and vibrated, in superstructure upto 4 meter above 1.50 m level from ground/bed level. [MoRTH Specification : Clause 1000/1700]	409.50 cum	3666.00	P.Cum	1501227.00
	1000mm dia HP 1 Row	225.36 cum	3666.00	P.Cum	826170.00
	1000mm dia HP 2 Row	41.48 cum	3666.00	P.Cum	152070.00
	Syphon	1531.25 cum	3666.00	P.Cum	5613563.00
	Retaining wall	629.53 cum	3666.00	P.Cum	2307857.00
	VCW	2837.12			10450882
9	Providing and laying Reinforced cement concrete pipes NP-3 for culverts including jointing ends and fixing collar with cement mortar 1:2. (MoRTH specification : clause 1000/2900). 1000mm dia	3.42 cum	3850.00	P.Cum	13167.00
	1000mm dia HP 1 Row	1.52 cum	3850.00	P.Cum	5852.00
	1000mm dia HP 2 Row	6.93 cum	3850.00	P.Cum	26695.00
	VCW	11.87			45210
10	Providing and laying Reinforced cement concrete pipes NP-3 for culverts including jointing ends and fixing collar with cement mortar 1:2. (MoRTH specification : clause 1000/2900) 500mm dia	30 135.00 RM	4410.00	RM	595350.00
	1000mm dia HP 1 Row	120.00 RM	4410.00	RM	529200.00
	1000mm dia HP 2 Row	75.00 RM	4410.00	RM	330750.00
	VCW	330.00			145300
	Syphon	60.00 RM	2243.00	RM	134580.00

No.	Description of Item	Quantity	Rate (Rs)	Unit	Amount (Rs)
1	2	3	4	5	6
11	Providing and laying RCC M-20 mix with stone aggregate 20mm (nominal size) mechanically mixed and vibrated for RCC work in slab in superstructure upto 4 mtr. above 1.5 mtr. level from Bed/Ground level, excluding steel reinforcement but including centering and shuttering, laid in position. (MoRTH specification : Clause 1000/1700)				
12	Plastering 20mm thick with cement mortar (1:3) on Masonry work in sub structure as per technical specifications.	2.10 cum	4528.00	P.Cum	9509.00
13	Structural cement concrete (Design Mix) in open foundations, with form work, at any level. Cement concrete for plain/reinforced concrete in open foundations as per drawing and technical specification. [MoRTH Specification : Section 1700 & 1500]. With 20mm nominal size aggregate P.C.C. M-15 grade	83.52 sqm. 161.66 sqm. <u>245.21</u>	139.00 139.00 <u>34084</u>	P.Sqm P.Sqm	11609.00 22475.00 <u>34084</u>
14	Structural cement concrete for plain concrete/ reinforced concrete for substructure at any level, complete as per drawing and technical specification. [MoRTH Specification : Section 1500 & 1700]. PCC M-25 grade Upto 5 mtr. Height	123.76 162.79 cum	3690.00	P.Cum	58427.00
15	Providing A.C. pipe Weep holes 150mm dia in Masonry/plain Concrete/Reinforced Concrete abutment, wing wall/return wall complete as per drawing and technical specification. [MoRTH Specification : Clause 2205].	342.34 352.95 cum <u>190 Cum</u>	3915.00	P.Cum	1381813.00
16	Steel reinforcement in substructure B-3 complete. [MoRTH Specification : Section 9.1 1600]	120.00 R.Mtr. 420.00 R.Mtr. 540.00	114.00 114.00	P.Mtr P.Mtr	13680.00 47880.00 <u>61560</u>
17	Providing and laying steel reinforcement at any level in foundation complete as per drawing and technical specification. [MoRTH Specification : Section 1600]. HYSD bar reinforcement	48.34 52.51 Tonne 4.40 Tonne <u>56.91</u>	88737.00 88737.00	P.Tonne P.Tonne	4659419.00 390731.00 <u>5050150</u>
		43.82 Tonne <u>42.79</u>	88667.00	P.Tonne	3881002.00

No.	Description of Item	Quantity	Rate (Rs.)	Unit	Amount (Rs.)
1	2	3	4	5	6
18 B-4 1.3. 1	Structural RCC/PSC upto a height of 5 mtr. for reinforced concrete in superstructure complete including steel formwork, scaffolding etc. As per drawing and technical specification. Design mix concrete. [MoRTH Specification : 1500 & 1700]. RCC M-30 grade Solid slab superstructure	211.57 211.58 cum	6307.00	P.Cum	1334422.00
	RCC Bridge				
19 B-4 4	Reinforced cement concrete wearing coat M-30 grade at any level including formwork and reinforcement complete as per drawing and technical Specification. [MoRTH Specification : Clause 2204, 1500 & 1700].	25.50 25.50 cum	7720.00	P.Cum	196860.00
	RCC Bridge				
20 B-4 15	Providing and Laying PCC M-15 grade leveling course below approach slab complete as per drawing and technical specifications. [MoRTH specification : 2700]	10.53 cum	2471.00	P.Cum	26020.00
	RCC Bridge				
21 B-4 16	Reinforced cement concrete M-30 grade approach slab including reinforcement and formwork complete as per drawing and technical specifications. [MoRTH specification : 1500, 1600, 1700, 2704]	21.05 21.06 cum	7073.00	P.Cum	148957.00
	RCC Bridge				
22 B-4 2	Providing and laying HYSD bar reinforcement at any level in superstructure complete as per drawing and technical Specification. [MoRTH Specification : Section 1600]	19.26 19.93 Tonne	89654.00	P.Tonne	1786862.00
	RCC Bridge				
23 B-3 17.17. 2	Providing and filling in foundation trenches, and back filling behind abutments, wing walls, return wall etc., and below pipe bed in layers not exceeding 150mm thick including watering and compacting (IRC-78) complete as per drawing and technical specifications (MoRTH specification 710 & 2200) including all lead and lifts. Selected granular Material in filling (MoRTH specification : Clause 2200).	243.75 246.32 cum	745.00	P.Cum	183508.00
	RCC Bridge				
24 B-1 4	Filter medium behind abutment, wing wall and return wall, complete as per drawing and technical specification. (Same as R7.20.3) [MoRTH Specification : Clause 2504].	83.16 cum	560.00	P.Cum	46570.00
	RCC Bridge				
25 B-4 10.1	Providing, laying and fixing of Filler Joint Providing and fixing 2mm thick Corrugated Copper Plate in expansion joint complete as per drawing and technical specifications in MoRTH specification : clause 2605.	25.5 25.50 Mtr	3673.00	P.Mtr	93662.00
	RCC Bridge				
26 R-9 59	Supply of flood gauge (water gauge) as per IRC 67 standard 200cm long fixed on angle iron posts 50x50x6mm 2.6m long	2.00 Nos	1383.00	Each	2766.00
	RCC Bridge				

121

लाने

को

121

121

1

3.No.	Description of Item	Quantity	Rate (Rs)	Unit	Amount (Rs)
1	2	3	4	5	6
27 R-7 2.1	Providing and Laying un-reinforced, dowel jointed, plain cement concrete pavement over a prepared sub-base with 43 grade cement, coarse and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25mm, mixed in a batching and mixing plant as per approved mix design, transported to site, laid with a fixed form or slip form paver, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, dowel bar, tie rod, admixtures and vacuum processing pump as approved, curing compound, finishing to lines and grades as per drawing as per MoRTH Specification : Clause No. 602, 112. Using Cement concrete M-20 pavement Grade				
	RCC Bridge	34.36			
		34.43 cum	4747.00	P.Cum	163415.00
8 B-5 4	Providing and laying graded stone aggregate filter Material underneath pitching on slopes complete as per drawing and technical specification. (MoRTH specification : clause 2504).				
	VCW	139.32 Cum	942.00	P.Cum	131239.00
			Total Rs.: 31415309.00		

Mahendra K...

[M.S. Saini]

Junior Engineer
PWD. Sub. Dn. Jhonthri

Pavan Kumawat
(Pavan Kumawat)
Assistant Engineer
PWD Sub Dn Jhonthri